

Tabela robót ziemnych
ul.Poleska

	Stat	NASYP		WYKOP	
	Odleg.	[M2/M3]	Odleg.	[M2/M3]	Odleg.
1	0+10,456	0,077		6,994	
	18,726	106,158	18,726	65,485	18,726
2	0+29,182	11,261		0,000	
	23,756	133,758	23,756	87,481	23,756
3	0+52,938	0,000		7,365	
	35,607	187,649	35,607	131,123	35,607
4	0+88,545	10,540		0,000	
	55,054	292,584	55,054	187,349	55,054
5	0+143,599	0,089		6,806	
	60,707	42,920	60,707	336,074	60,707
6	0+204,306	1,325		4,266	
	50,882	34,880	50,882	299,670	50,882
7	0+255,188	0,046		7,513	
	40,650	7,114	40,650	260,627	40,650
8	0+295,838	0,304		5,310	
	49,928	12,108	49,928	209,723	49,928
9	0+345,766	0,181		3,091	
	49,840	19,637	49,840	135,241	49,840
10	0+395,606	0,607		2,336	
	51,873	45,700	51,873	114,147	51,873
11	0+447,479	1,155		2,065	
	52,449	41,881	52,449	161,543	52,449
12	0+499,928	0,442		4,095	
	50,045	11,060	50,045	252,752	50,045
13	0+549,973	0,000		6,006	
	50,782	24,807	50,782	188,681	50,782
14	0+600,755	0,977		1,425	
	50,889	59,438	50,889	81,448	50,889
15	0+651,644	1,359		1,776	
	28,856	19,608	28,856	78,517	28,856
16	0+680,500	0,000		3,666	
		1039,3 NASYP	2589,86 WYKOP		
		[M2/M3]	[M2/M3]		